



# Test Report: GST25U12-P1J

---

25W AC-DC Reliable Green Industrial Adaptor

## ■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

## ■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

## ■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

**OUTPUT FUNCTION TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE(Max)	V1:80 mVp-p	I/P : 230VAC O/P:FULL LOAD Ta:25°C	V1:32mVp-p	P
2	OUTPUT VOLTAGE(Max) TOLERANCE	V1: 3%~ -3%	I/P: 85VAC /264VAC O/P:FULL/ MIN. LOAD Ta:25°C	V1: -0.67 %~0%	P
3	LINE REGULATION (Max)	V1: 1%~ -1%	I/P: 85 VAC~ 264VAC O/P:FULL LOAD Ta:25°C	V1: 0%~0%	P
4	LOAD REGULATION(Max)	V1:3%~ -3%	I/P: 230VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: -0.34%~0.33%	P
5	SET UP TIME(Max)	230VAC/1000 ms 115VAC/1500 ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/660ms 115VAC /840 ms	P
6	RISE TIME (Max)	230VAC/30 ms 115VAC/30 ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/5.4 ms 115VAC /9.2 ms	P
7	HOLD UP TIME(Typ)	230VAC/50 ms 115VAC/15 ms	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/79.2 ms 115VAC /17.6 ms	P
8	OVER/UNDERSHOOT TEST	< +5%	I/P: 230VAC O/P:FULL LOAD Ta:25°C	<-0.75%	P
9	DYNAMIC LOAD	V1: 1200 mVp-p	I/P: 230VAC O/P(1)FULL /Min LOAD 90%DUTY / 1KHZ (2) (1)FULL /Min LOAD 90%DUTY / 3KHZ (3)FULL /Min LOAD 90%DUTY / 5KHZ (4)FULL /Min LOAD 50%DUTY / 120HZ Ta:25°C	360mVp-p 292mVp-p 284mVp-p 420mVp-p	P

**INPUT FUNCTION TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
----	-----------	---------------	----------------	--------	---------

1	INPUT VOLTAGE RANGE	85VAC~264VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	72V~264V	P
			I/P: (1)LOW-LINE-3V=82V HIGH-LINE+15%=300 V O/P:FULL/MIN LOAD ON: 30 Sec OFF: 30 Sec 10MIN (2)230Vac ON: 0.5 Sec OFF: 0.5 Sec 20MIN (3)230Vac ON:3Sec OFF:3Sec 12HOURS (POWER ON/OFF NO DAMAGE )	TEST:OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P:85 VAC ~264 VAC O/P:FULL~MIN LOAD Ta:25°C	TEST: OK	P
3	EFFICIENCY(TYP)	86.5%	I/P:230 VAC I/P:115 VAC O/P:FULL LOAD Ta:25°C	87.07%	P
4	INPUT CURRENT (Typ)	230V/ 0.35 A 115V/ 0.60 A	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I =0.284A/ 230VAC I =0.456A/ 115VAC	P
5	INRUSH CURRENT(Typ)	230V/ 65 A 115V/ 35 A COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I =60.7A/ 230VAC I =32.5A/ 115VAC	P
6	LEAKAGE CURRENT	< 0.25 mA / 240 VAC	I/P : 240 VAC O/P : Min LOAD Ta : 25°C	L-FG : 0.001 mA N-FG : 0.001 mA	P
7	NO LOAD CONSUMPTION	< 0.075 W	I/P : 115VAC I/P : 230VAC O/P : NO LOAD Ta : 25°C	<0.034 W <0.041 W	P

**PROTECTION FUNCTION TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	110 %~ 150 %	I/P: 230VAC I/P: 115VAC O/P: TESTING Ta:25°C	130.13%/ 230VAC 133.25%/115VAC Hiccup mode, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	110 ~ 140% rated output voltage Clamp by zener diode	I/P: 230VAC I/P: 115VAC O/P: MIN LOAD Ta:25°C	128.5%/ 230VAC 128.5%/115VAC Clamp by zener diode	P
3	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 264VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Hiccup mode, recovers automatically after fault condition is removed	P

**COMPONENT STRESS TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	PWM Transistor ( D to S) or (C to E) Peak Voltage	Q 1 Rated 6A/600V	I/P: High-Line +3V =267V AC ON/OFF VDS: O/P: (1) Full Load (2) Output Short (3) Full Load Continue Ta:25°C	Q1: (1) 548 V (2) 523V (3) 542V	P
2	Diode Peak Voltage	D100 Rated 20A/100V	I/P: High-Line +3V =267 V AC ON/OFF O/P: (1) Full Load (2) Output Short (3) Dynamic Load Full Load/ Min. Load 90%Duty/5KHz (4) Dynamic Load 100% Load/ Min. Load 50%Duty/120Hz Ta:25°C	D100 : (1) 96.8V (2) 99.2V (3) 90.0V (4) 94.8V	P
3	Input Capacitor Voltage	C5 Rated: 47u/400V 105°C	I/P: High-Line +3V =267 V O/P: (1) Full Load input on/off (2) Min load input on /Off (3) Full Load /Min load Change Ta:25°C	(1) 374V (2) 378V (3) 378V	P
4	Control IC Voltage Test	PWM IC U1 Rated : 27V 10V(MIN.)	I/P: High-Line +3V =267 V AC ON/OFF O/P: (1) FULL LOAD (2) Output Short (3) O.L.P (4) NO LOAD VR MIN LOW LINE Ta:25°C	(1) 13.0V (2) 16.8V (3) 16.8V (4) 10.3V	P

5	Clamp Diode Peak Voltage	D1 Rated : 2A/800V	I/P : High-Line +3V = 267 V AC ON/OFF O/P : (1) Dynamic Load 90%Duty/1KHz (2) Full load continue Ta : 25°C	(1) 446 V (2) 448 V	P
---	--------------------------	--------------------	---	------------------------	---

**SAFETY TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 4.242 KVDC/min	I/P-O/P: 4.666 KVDC/min Ta:25°C	I/P-O/P:0.002mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ	I/P-O/P: 500 VDC Ta:25°C	I/P-O/P: 9999MΩ NO DAMAGE	P

**E.M.C TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CONDUCTION	FCC PART 15 / CISPR22, CAN ICES-3(B)/NMB-3(B) CNS13438, EAC TP TC 020 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL/50% LOAD Ta : 25°C	PASS Test by certified Lab	P
2	RADIATION	FCC PART 15 / CISPR22, CAN ICES-3(B)/NMB-3(B) CNS13438, EAC TP TC 020 CLASS B	I/P : 230 VAC (50HZ) O/P : FULL LOAD Ta : 25°C	PASS Test by certified Lab	P
3	Test by certified Lab & Test Report Prepare				

**RELIABILITY TEST**

**ENVIRONMENT TEST**

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : GST25U12-P1J 1. ROOM AMBIENT BURN-IN : 1HRS I/P : 230VAC O/P : FULL LOAD Ta=31.0°C 2. HIGH AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta=56.1°C			P

2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )	I/P : 230 VAC O/P : 132% LOAD Ta : 25°C	TEST : OK	P
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 100 % LOAD Ta=-35°C	TEST : OK	P
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 50°C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta=50°C HUMIDITY= 95 %R.H	TEST : OK	P
5	TEMPERATURE COEFFICIENT	±0.03%/°C (0~50°C)	I/P : 230 VAC O/P : FULL LOAD	±0%/°C (0~50°C)	P
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -40°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK	P
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -30°C~ +70°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec		OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	P
9	CAPACITOR LIFE CYCLE	SUPPOSE C105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25°C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=50°C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=50°C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta=50°C LIFE TIME		(1) 257261HRS (2) 50068HRS (3) 76969HRS (4) 129454HRS	P
10	MTBF	3879.7K hrs min. Telcordia SR-332 (Bellcore) ; 674.6K hrs min. MIL-HDBK-217F (25 )			P
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure (Expected Life): Above 50,000 hours @ TA 50°C			P

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	FRANK	GESG	WANGDZ

2007/3/20 A50-S014