



# Test Report: HEP-100-12

---

100W Single Output Switching Power Supply

## ■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

## ■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

## ■ RELIABILITY TEST



## DESIGN VERIFY TEST

## OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	RIPPLE & NOISE	V1: 120 mVp-p (Max)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	V1: 20.3 mVp-p (Max)
2	OUTPUT VOLTAGE ADJUST RANGE	CH1: 10.8V~13.5 V	I/P: 230 VAC I/P:115VAC O/P:MIN LOAD Ta:25°C	10.527 V~13.841 V /230VAC 10.525 V~13.841 V/115VAC
3	CURRENT ADJ RANGE	5A~8.34A	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	3.96A~ 10.76 A
4	OUTPUT VOLTAGE TOLERANCE	V1: -1% ~ 1% (Max)	I/P: 100 VAC /305VAC O/P:FULL/ 0% LOAD Ta:25°C	V1: -0.6 %~0.6 %
5	LINE REGULATION	V1: -0.5% ~ 0.5% (Max)	I/P:100 VAC ~305 VAC O/P:FULL LOAD Ta:25°C	V1: -0.06 %~0.06 %
6	LOAD REGULATION	V1: -2% ~ 2% (Max)	I/P: 230 VAC O/P:FULL ~MIN LOAD Ta:25°C	V1: -0.52 %~0.52 %
7	SET UP TIME	230VAC/ 500 ms (Max) 115VAC/ 1200 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 394 ms 115 VAC/ 824 ms
8	RISE TIME	230VAC/ 50 ms (Max) 115VAC/ 50 ms (Max)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 9.6 ms 115 VAC/ 9.5 ms
9	HOLD UP TIME	230VAC/ 16 ms (Typ) 115VAC/ 16 ms (Typ)	I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	230VAC/ 23 ms 115 VAC/ 23 ms
10	OVER/UNDERSHOOT TEST	< ±5%	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	TEST:< 5 %
11	DYNAMIC LOAD	V1: 1200 mVp-p	I/P: 230 VAC O/P:(1)FULL /Min LOAD 90%DUTY/1KHZ (2)FULL /Min LOAD 90%DUTY/120HZ Ta:25°C	818 mVp-p 852 mVp-p

## INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	INPUT VOLTAGE RANGE	90VAC~305 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	79 V~305V
			I/P: (1)LOW-LINE-3V=87 V (2)HIGH-LINE+10V=315 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN ( AC POWER ON/OFF NO DAMAGE )	TEST: OK
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE	I/P: 100 VAC ~305VAC O/P:FULL~MIN LOAD Ta:25°C	OK
3	POWER FACTOR	0.95/ 230 VAC FULL LOAD (TYP) 0.98/ 115 VAC FULL LOAD (TYP) 0.93/ 277 VAC FULL LOAD (TYP)	I/P: 230 VAC I/P: 115 VAC I/P: 277 VAC O/P:FULL LOAD Ta:25°C	PF=0.9627/230V/100%LOAD PF=0.9946 /115V/100%LOAD PF=0.94 /277V/100%LOAD
4	EFFICIENCY	92% (TYP)	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	92.05 %
5	INPUT CURRENT	277V/ 0.5 A (TYP) 230 V/ 0.55 A (TYP) 115 V/ 1.2 A (TYP)	I/P: 277 VAC I/P: 230 VAC I/P: 115 VAC O/P:FULL LOAD Ta:25°C	I = 0.4 A/ 277VAC I = 0.497 A/ 230VAC I = 0.969 A/ 115VAC
6	INRUSH CURRENT	230 V/ 60A (Typ) COLD START	I/P: 230 VAC O/P:FULL LOAD Ta:25°C	I = 48 A/ 230VAC

## PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	OVER LOAD PROTECTION	105 %~125 %	I/P: 305VAC I/P: 230 VAC I/P: 100 VAC O/P:TESTING Ta:25°C	110 %/305VAC 110 %/ 230VAC 110 %//100VAC Constant Current Limiting
2	OVER VOLTAGE PROTECTION	V1: 14V~ 17V	I/P: 305VAC I/P: 230 VAC I/P: 90 VAC O/P:MIN LOAD Ta:25°C	15.1 V/ 305VAC 15.2 V/ 230VAC 15.2 V/ 100VAC Shut down o/p voltage with auto recovery or re-power on to recovery
3	OVER TEMPERATURE PROTECTION	Shut down o/p voltage with auto recovery or re-power on to recovery	I/P: 230 VAC O/P:FULL LOAD	O.T.P. Active Shut down o/p voltage with auto recovery or re-power on to recovery
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P: 305VAC O/P: FULL LOAD Ta:25°C	NO DAMAGE Constant Current Limiting

## COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	Power Transistor ( D to S) or (C to E) Peak Voltage	Q5 Rated 12A/500V	I/P : High-Line +3V = 308V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 468 V (2) 466 V (3) 458 V
2	Diode Peak Voltage	Q101 Rated 202A/40V	I/P : High-Line +3V =308V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 34 V (2) 35.1 V (3) 32.8 V
		Q102 Rated 202A/40V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 33.6 V (2) 35.6 V (3) 33.5 V
3	Input Capacitor Voltage	C5 Rated: 82u/450V	I/P : High-Line +3V = 308V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 436.8 V (2) 437.3 V (3) 450.1 V
4	Control IC Voltage Test	U 900 Rated 8.85V~16V	I/P : High-Line +3V = 308V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 14.1 V (2) 14 V (3) 14 V
5	P.F.C Transistor ( D to S) or (C to E) Peak Voltage	Q1 Rated 17A/600V	I/P : High-Line +3V = 308 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 482 V (2) 474 V (3) 478 V

## SAFETY & EMC TEST

### SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	WITHSTAND VOLTAGE	IEC60950-1 I/P-O/P: 3.75KVAC/min I/P-FG:2 KVAC/min O/P-FG:1.5KVAC/min	I/P-O/P: 4 KVAC/min I/P-FG: 2.4KVAC/min O/P-FG:1.8 KVAC/min Ta:25°C	I/P-O/P: 2.612 mA I/P-FG: 2.350 mA O/P-FG: 3.62 mA NO DAMAGE
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>100MΩ I/P-FG: 500VDC>100MΩ O/P-FG:500VDC>100MΩ	I/P-O/P: 500 VDC I/P-FG: 500 VDC O/P-FG: 500 VDC Ta:25°C	I/P-O/P: 30 GΩ I/P-FG: 11 GΩ O/P-FG: 30 GΩ NO DAMAGE
3	GROUNDING CONTINUITY	IEC60950-1 FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40A / 2min Ta:25°C	11 mΩ
4	LEAKAGE CURRENT	IEC60950-1 < 0.75 mA / 277VAC	I/P: 277 VAC O/P:Min LOAD Ta:25°C	L-FG: 0.27 mA N-FG: 0.27 mA

### E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT
1	HARMONIC	EN61000-3-2 CLASS A	I/P: 240VAC/50HZ O/P:100%/50% LOAD Ta:25°C	PASS
2	CONDUCTION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab
3	RADIATION	EN55022 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab
4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT : 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A
6	SURGE	IEC61000-4-5 INDUSTRY L-N : 3KV L,N-PE:6KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A

## Reliability Test

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT																																																																
1	TEMPERATURE RISE TEST	MODEL : HEP-100-24 1. ROOM AMBIENT BURN-IN : 2.5 HRS I/P : 230VAC O/P : FULL LOAD Ta= 30.7 °C 2. HIGH AMBIENT BURN-IN : 5.5 HRS I/P : 230VAC O/P : FULL LOAD Ta=60.7 °C	<table border="1"> <thead> <tr> <th>NO</th> <th>Position</th> <th>ROOM AMBIENT Ta= 30.7 °C</th> <th>HIGH AMBIENT Ta= 60.7 °C</th> </tr> </thead> <tbody> <tr><td>1</td><td>BD1</td><td>46.8°C</td><td>74.8°C</td></tr> <tr><td>2</td><td>Q1</td><td>48.1°C</td><td>76.1°C</td></tr> <tr><td>3</td><td>L2</td><td>48.8°C</td><td>76.8°C</td></tr> <tr><td>4</td><td>Q5</td><td>48.2°C</td><td>76.2°C</td></tr> <tr><td>5</td><td>D2</td><td>48.8°C</td><td>76.8°C</td></tr> <tr><td>6</td><td>RTH2</td><td>46.3°C</td><td>74.3°C</td></tr> <tr><td>7</td><td>C5</td><td>45.5°C</td><td>73.5°C</td></tr> <tr><td>8</td><td>T1</td><td>49.3°C</td><td>77.3°C</td></tr> <tr><td>9</td><td>Q101</td><td>47.4°C</td><td>75.4°C</td></tr> <tr><td>10</td><td>D9</td><td>47.0°C</td><td>75.0°C</td></tr> <tr><td>11</td><td>C102</td><td>45.3°C</td><td>73.3°C</td></tr> <tr><td>12</td><td>C201</td><td>46.3°C</td><td>74.3°C</td></tr> <tr><td>13</td><td>C38</td><td>48.2°C</td><td>76.2°C</td></tr> <tr><td>14</td><td>U900</td><td>47.4°C</td><td>75.4°C</td></tr> <tr><td>15</td><td>U1</td><td>49.4°C</td><td>77.4°C</td></tr> </tbody> </table>	NO	Position	ROOM AMBIENT Ta= 30.7 °C	HIGH AMBIENT Ta= 60.7 °C	1	BD1	46.8°C	74.8°C	2	Q1	48.1°C	76.1°C	3	L2	48.8°C	76.8°C	4	Q5	48.2°C	76.2°C	5	D2	48.8°C	76.8°C	6	RTH2	46.3°C	74.3°C	7	C5	45.5°C	73.5°C	8	T1	49.3°C	77.3°C	9	Q101	47.4°C	75.4°C	10	D9	47.0°C	75.0°C	11	C102	45.3°C	73.3°C	12	C201	46.3°C	74.3°C	13	C38	48.2°C	76.2°C	14	U900	47.4°C	75.4°C	15	U1	49.4°C	77.4°C	
NO	Position	ROOM AMBIENT Ta= 30.7 °C	HIGH AMBIENT Ta= 60.7 °C																																																																	
1	BD1	46.8°C	74.8°C																																																																	
2	Q1	48.1°C	76.1°C																																																																	
3	L2	48.8°C	76.8°C																																																																	
4	Q5	48.2°C	76.2°C																																																																	
5	D2	48.8°C	76.8°C																																																																	
6	RTH2	46.3°C	74.3°C																																																																	
7	C5	45.5°C	73.5°C																																																																	
8	T1	49.3°C	77.3°C																																																																	
9	Q101	47.4°C	75.4°C																																																																	
10	D9	47.0°C	75.0°C																																																																	
11	C102	45.3°C	73.3°C																																																																	
12	C201	46.3°C	74.3°C																																																																	
13	C38	48.2°C	76.2°C																																																																	
14	U900	47.4°C	75.4°C																																																																	
15	U1	49.4°C	77.4°C																																																																	
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR ( MIN )	I/P : 305 VAC O/P : O/P SHORT TEST Ta : 25°C	TEST : OK																																																																
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 305VAC/230VAC/100VAC O/P : 100% LOAD Ta= -55 °C	TEST : OK																																																																
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 60 °C NO DAMAGE	I/P : 305 VAC O/P : 100% Ta= 60 °C HUMIDITY= 95 %R.H	TEST : OK																																																																
5	TEMPERATURE COEFFICIENT	± 0.03 %(0~50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.002 %(0~50°C)																																																																
6	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -60°C~+90°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC		OK																																																																
7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -55°C~+65°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load TURN ON/58 'SEC.;TURN OFF/2SEC.		OK																																																																



# 100W Single Output Switching Power Supply

# HEP-100 series

8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 20~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 10G (5) Test Time : 72min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK
9	CAPACITOR LIFE CYCLE	HEP-100-24:SUPPOSE C102 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 60 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 60 °C LIFE TIME (4) I/P : 230VAC O/P : 50% LOAD Ta= 60 °C LIFE TIME	(1) 1380862 HRS (2) 140238 HRS (3) 161122 HRS (4) 172705 HRS
10	MTBF	Conducted by Parts Stress Analysis Prediction 1970.2K hrs min. Telcordia SR-332 (Bellcore) ; 164.8K hrs min. MIL-HDBK-217F (25°C)	OK
11	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 55,000 hours @ Tcase 80°C	OK

TEST RESULT	TESTER	REVIEW	APPROVAL
PASS	DANIEL GAO	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023