

MODEL : SE-450-5

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 200 mVp-p (Max)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	V1 : 160 mVp-p (Max)	PASS
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 4.5 V~ 5.5 V	I/P : 230 VAC I/P : 115VAC O/P : MIN LOAD Ta : 25°C	4.345V~5.816V /230Vac 4.344V~5.815 V /115VAC	PASS
3	OUTPUT VOLTAGE TOLERANCE	V1 : -3 %~ +3 % (Max)	I/P : 200VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : -1.376 %~ +1.117 %	PASS
4	LINE REGULATION	V1 : -0.5 %~ +0.5 % (Max)	I/P : 200 VAC ~ 264VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~+0.120 %	PASS
5	LOAD REGULATION	V1 : -2 %~ +2 % (Max)	I/P : 230 VAC O/P : FULL -MIN LOAD Ta : 25°C	V1 : -0.735 %~+0.735 %	PASS
6	SET UP TIME	230VAC/ 1500 ms (Max) 115VAC/ 1500 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230 VAC/ 92.7 ms 115 VAC/ 86.5 ms	PASS
7	RISE TIME	230VAC/ 50 ms (Max) 115VAC/ 50 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230 VAC/ 1.6 ms 115 VAC/ 2.2 ms	PASS
8	HOLD UP TIME	230VAC/ 16 ms (Typ) 115VAC/ 12 ms (Typ)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 30.4 ms 115 VAC/ 25.5 ms	PASS
9	OVER/UNDERSHOOT TEST	< ±10%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : +3.98 % -1.20 %	PASS
10	DYNAMIC LOAD	V1 : 1000 mVp-p	I/P : 230 VAC O/P: (1)FULL /Min LOAD 90%DUTY/1KHZ (2)FULL /Min LOAD 50%DUTY/120HZ Ta : 25°C	(1) 320 mVp-p (2) 350 mVp-p	PASS

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	180 VAC~ 264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	170 V~ 264 V	PASS
			I/P : LOW-LINE-3V= 177 V HIGH-LINE+15%= 300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 180 VAC ~264 VAC O/P : FULL-MIN LOAD Ta : 25°C	TEST : OK	PASS
3	EFFICIENCY	78 % (Typ)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	80.23 %	PASS
4	INPUT CURRENT	230 V/ 6 A (Typ) 115 V/ 10 A (Typ)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 3.23 A/ 230VAC I = 5.57 A/ 115VAC	PASS
5	INRUSH CURRENT	230 V/ 55 A (Typ) 115 V/ 35 A (Typ) COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 33.0 A/ 230VAC I = 22.9 A/ 115VAC	PASS

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105%-150% RATED OUTPUT POWER	I/P : 264 VAC I/P : 230 VAC I/P : 200 VAC O/P : TESTING Ta : 25°C	131 %/264VAC 123 %/ 230VAC 116 %/200 VAC Shut down Re-power ON	PASS
2	OVER VOLTAGE PROTECTION	CH1 : 5.75 V~ 6.75 V	I/P : 264 VAC I/P : 230 VAC I/P : 180 VAC O/P : MIN LOAD Ta : 25°C	6.22 V/ 264VAC 6.22 V/ 230VAC 6.22 V/ 180VAC Shut down Re-power ON	PASS
3	OVER TEMPERATURE PROTECTION	SPEC : TSW1 : 80±5 °C O.T.P. NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage , recovers automatically after temperature goes down	PASS
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Shut down Re-power ON	PASS

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	REMOTE SENSE	S+ / S- >0.25V	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	0.94 V	PASS

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : SE-450-5 1. ROOM AMBIENT BURN-IN : 1 HRS I/P : 230VAC O/P : FULL LOAD Ta= 36.2 °C 2. HIGH AMBIENT BURN-IN : 2 HRS I/P : 230VAC O/P : FULL LOAD Ta=46.2 °C			PASS
2	OVER LOAD BURN-IN TEST	NO DAMAGE 1 HOUR (MIN)	I/P : 230 VAC O/P : 110 % LOAD Ta : 25°C	TEST : OK	PASS
3	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 230 VAC O/P : 100 % LOAD Ta= -25 °C	TEST : OK	PASS
4	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 45 °C NO DAMAGE	I/P : 272 VAC O/P : FULL LOAD Ta= 45 °C HUMIDITY= 95 %R.H	TEST : OK	PASS
5	TEMPERATURE COEFFICIENT	± 0.05 % (0-50°C)	I/P : 230 VAC O/P : FULL LOAD	± 0.008 % (0-50°C)	PASS
6	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 10min/sweep cycle (4) Acceleration : 2G (5) Test Time : 1 hour in each axis (X.Y.Z) (6) Ta : 25°C		TEST : OK	PASS

M.T.B.F & LIFE CYCLE CALCULATION

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	CAPACITOR LIFE CYCLE	SE-450-5 : SUPPOSE C 105 IS THE MOST CRITICAL COMPONENT I/P : 230 VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME= 232862.7 HRS I/P : 230 VAC O/P : FULL LOAD Ta= 45 °C LIFE TIME=34594.7 HRS			PASS
2	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 200K HRS			PASS

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-FG : 1.5 KVAC/min I/P-O/P : 3.0 KVAC/min O/P-FG : 0.5 KVAC/min	I/P-FG : 1.6 KVAC/min I/P-O/P : 3.1 KVAC/min O/P-FG : 0.6 KVAC/min Ta : 25°C	I/P-FG : 5.12 mA I/P-O/P : 6.09 mA O/P-FG : 3.97 mA NO DAMAGE	PASS
2	ISOLATION RESISTANCE	I/P-FG : 500VDC>100MΩ I/P-O/P : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-FG : 500 VDC I/P-O/P : 500 VDC O/P-FG : 500 VDC Ta : 25°C	I/P-FG : 1982 MΩ I/P-O/P : >9999 MΩ O/P-FG : 1791 MΩ NO DAMAGE	PASS
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	25A / 1min Ta : 25°C	6 mΩ	PASS
4	LEAKAGE CURRENT	< 2.5 mA / 240VAC	I/P : 264 VAC O/P : NO LOAD Ta : 25°C	L-FG : 1.00 mA N-FG : 1.01 mA	PASS

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 1/2 Rated IRFP460 : 500 V / 20 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load 50% Load/ Min. Load 90%Duty/1KHz Ta : 25°C	Q1 Q2 (1) 392 V (1) 426 V (2) 0 V (2) 0 V (3) 394 V (3) 430 V (4) 378 V (4) 396 V	PASS
2	Diode Peak Voltage	D 100 Rated S60SC6M : 60 V / 60 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (4)Dynamic Load 50% Load/ Min. Load 90%Duty/1KHz Ta : 25°C	(1) 41.0 V (2) 0 V (3) 39.8 V (4) 41.2 V	PASS
3	Clamp Diode Peak Voltage	D15/16 Rated 31DF6 : 600 V / 3 A	I/P : High-Line +3V = 267 V O/P : (1)Dynamic Load Full Load/ Min. Load 90%Duty/1KHz (2)Dynamic Load 50% Load/ Min. Load 90%Duty/1KHz Ta : 25°C	D15 D16 (1) 354 V (1) 354 V (2) 360 V (2) 360 V	PASS
4	Control IC Voltage Test	U 1 Rated TL3843P : 30 V	I/P : High-Line +3V =267 V O/P : (1) Output Short (2)O.L.P Ta : 25°C	(1) 9.80 V (2) 9.80 V	PASS

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2008.11.7	RD SAMPLE	PASS	SKY	LIUWY

2003/12/12 A50-F023